

# How Omikron Works

The engine of *Omikron: The Nomad Soul* (1999), and the replica that runs it again

A book for developers, to be read in order

*Draft of 2026-10-03*

# Contents

---

Before you start

## **Part I — The game as a machine**

1. A machine and its content
2. One frame
3. Where the game lives

## **Part II — How the world behaves**

4. A tiny computer inside the game
5. Places
6. Bodies
7. Stories: conversations and cutscenes

## **Part III — Pictures and sound**

8. Drawing a frame in 1999
  9. Sound without a mixer
  10. The interface
- Interlude — one frame in Anekbah

## **Part IV — Reading a binary**

11. How you read an engine without its source

## **Part V — Rebuilding it**

12. The shape of the replica
13. Running the world
14. Four renderers, and two faces in the same place
15. Making it fast
16. Where to go from here

# Before you start

---

## Who this is for

You write games or tools. Maybe you know Unity well, you have read some assembly, written some C and C++, and pushed triangles through OpenGL. You have never looked inside a 1999 engine, and you would like to understand one properly: not the list of its file formats, but *why it is built the way it is*, and what it takes to rebuild it on hardware its authors never saw.

That is what this book tries to give you. It follows one game, *Omikron: The Nomad Soul*, from the moment its executable starts to the moment a pixel reaches the screen, and then follows the project that reverse-engineered it (OMK) through the rebuilding.

## How it differs from the manual

This repository already has a **manual** (`manual/`): thirteen chapters, each with a plain summary and a technical account, the addresses of the functions, the offsets of the fields, the checks that assert every number. It is a reference. You go to it with a question.

This book is the other thing. It is meant to be read **from the first page to the last**, and each chapter leans on the ones before it. It uses fewer numbers, and only the ones that carry an idea. It explains mechanisms with pictures and analogies, and when it needs a precise fact it tells you which chapter of the manual, or which document under `docs/`, holds it. If the two ever disagree, the documents under `docs/` win: this book, like the manual, is *derivative*, a retelling of findings recorded elsewhere with their evidence.

## How it is organised

**Part I** looks at the game as a machine: what the executable is, what one frame does, and where the game really lives, which is in its data files.

**Part II** is about behaviour: the tiny computer inside the game that runs its scripts, the places the world is made of, the bodies that walk around in them, and the stories told with conversations and cutscenes.

**Part III** is about output: how a frame was drawn in 1999, how sound works without a mixer, and how the interface is built.

**Part IV** is short and a little different: how you read an engine you do not have the source code of, and how you know when you have read it right.

**Part V** is the rebuilding: the shape of the replica, the renderers behind it, the long work of making it fast enough for a handheld, and how that work compares with what the original engine did.

Throughout, boxes like this one translate an idea into terms you may already know:

**From Unity:** a box like this maps an Omikron mechanism onto the closest Unity or OpenGL concept. The mapping is never exact, and the box says where it breaks.

## A running example

One scene comes back again and again: **Kay'l standing in Anekbah's main street**, the city's crowd walking past, a street lamp glowing, a shop sign hanging on a wall. It is the port's standard test scene, and nearly every subsystem in this book shows up in it somewhere. When a chapter introduces a mechanism, it will usually tell you where that mechanism is in this street.

## **Part I — The game as a machine**

# 1. A machine and its content

---

## Three games in one coat

*Omikron: The Nomad Soul* was made by Quantic Dream and published by Eidos in 1999 for Windows. It is an adventure game in which you walk through a city and talk to people; a beat-'em-up in which you fight them hand to hand; and a first-person shooter in which you shoot them. Now and then you swim. Its central idea is that you are a soul that can move from one body to another, so the game must be able to hand you a different character at any moment and carry on.

A game with that much in it sounds like it should need a very large program. It does not. The executable is about **985 KB**. Everything else, about **1.7 GB in 2 812 files**, is data.

## The split that makes it readable

What is compiled into the executable is not the game. It is a **machine**:

- an interpreter for a small bytecode language, which runs the game's scripts;
- a runner for state graphs, which moves the characters' bodies;
- a renderer, a sound bank and a 2D interface layer;
- one reader for each file format.

What the game *does* is all in the data. Which conversation starts when you walk through a doorway, which camera watches it, which animation a character plays when it turns round, which gunman patrols which corridor: those are scripts, state graphs, meshes and tables in the files beside the executable.




Figure 1 — The executable is the machine; the data is the game.

This split is the single most important fact in the book, because it is what made the whole reverse-engineering project possible. Read the machine once, carefully, and the content reads itself: 5 785

scripts, 320-odd conversations and hundreds of models become understandable, because they are all run by the same few hundred functions.

**From Unity:** think of the executable as the Unity player, the compiled runtime you never edit, and of the data as the scenes, prefabs, animator controllers and assets of a built game. The difference is that Omikron's "player" was written for one game only, so its data formats encode that game's ideas directly: a trigger zone, a conversation, a fight.

## What OMK is

OMK is the project this repository holds. It has two halves:

1. **The reading.** The findings about how the original engine works, each one tied to the function in the executable that establishes it. They live in `docs/`, and roughly five hundred automatic checks (`tools/verify.py`) keep every number in them honest.
2. **The replica.** `engine/` is a new implementation of the machine, written in C++20, which reads *your* copy of the game's data and runs it. It contains no game content and never will.

The replica is not an emulator. It does not execute the original machine code. It re-implements what that code *decides* (which script runs, which state a body enters, which triangles are drawn in which order) and uses today's hardware to carry out those decisions.

## The words you will need

A handful of the game's own terms come back throughout:

| term    | what it is                                                                                                            |
|---------|-----------------------------------------------------------------------------------------------------------------------|
| area    | a place, such as a street, a flat or a corridor, stored as one chunk of an archive                                    |
| scene   | a second layer of content that can be loaded over an area: the cutscene material for a particular moment of the story |
| set     | the 3D model of a place: its walls, floors, signs and lamps                                                           |
| zone    | an invisible box on the floor that runs a script when you enter it, act inside it or leave it                         |
| context | one running script, with its own program counter and stack                                                            |
| channel | the state-graph runner attached to one body                                                                           |
| slider  | the flying car of the game's cities                                                                                   |
| sneak   | Kay's handheld device: the inventory, the map, the notes                                                              |

You do not need to remember them now. Each gets its own explanation when the story reaches it.

## 2. One frame

---

### The loop

Double-click the icon and the executable does five things in order. It starts its subsystems. It plays three videos (Eidos, Quantic Dream, then a title sequence). It loads a scene file called `aventure.scx`. It shows a splash bitmap. Then it enters a loop that runs one frame at a time until you quit.

That loop is an ordinary Windows message pump. The game only runs a frame when the pump has **nothing else to do**, and only while the window is in the foreground. Switch to another application and the loop calls `WaitMessage()`, which really blocks: the process stops using the processor. When you come back, the first thing the next frame does is **throw away** the time that passed. Without that, returning after a two-minute break would hand the simulation a two-minute step.





Figure 2 — One frame: the clock, the input, the scripts, the bodies, the scene, the draw.



*The start menu in the game's invented alphabet: a frame of the original engine's own framebuffer, captured at  $640 \times 480$  (`traces/frames/menu-22.png`).*

`aventure.scx` deserves a note, because its name suggests a menu. It is not one. It is the game's global library of effect sprites and sounds. There is no "menu state" in this engine. The start menu is a screen opened by the first area's own startup script, over an ordinary scene: the same machinery that later runs a street. Chapter 5 shows how.

## The clock counts frames

Every clock in the engine (animations, camera moves, the flicker of a neon sign) is measured in **frames at 30 Hz**, not in seconds. That comes from one line in the frame function, which sets the time step to

```
dt = 30 / fps
```

At exactly 30 frames per second, `dt` is 1.0. At 60 it is 0.5, and every clock advances half a frame per rendered frame, so the game runs at the same speed at any rate. This is why durations everywhere in this repository are quoted in frames. A clip "136 frames long" is four and a half seconds.

It does not quite *look* the same, though. A body's pose is taken from its clip by truncating the clock to a whole key, so at 60 frames per second each key is simply shown twice. The port does the same by default; drawing the in-between poses is one of its enhancements (chapter 12).

There is one more rule, and it matters for a slow machine: **`dt` is capped at 3.0**. Below 10 frames per second the game does not take larger steps. It slows down. A replica that integrated real elapsed time on a slow console would not be more accurate; it would be doing something the original never did.

The port learned this the hard way. On a PS Vita running at 200–300 ms a frame, an earlier clamp of its own made the camera visibly "shake"; replacing it with the engine's own cap of three frames fixed it.

**From Unity:** `dt` is the engine's `Time.deltaTime`, but expressed in thirtieths of a second and clamped at 0.1 s, the equivalent of setting `Time.maximumDeltaTime`. There is no separate `FixedUpdate`: the whole game steps once per rendered frame, on this one variable.

## Two details at the edge of the loop

**Escape is not a key the game binds.** The loop reads it directly, just before the frame, and opens the pause screen itself. The pause does more than set a flag: the pause screen's open callback suspends every sound buffer and music stream, and its close resumes them from where they were.

**The intro films have two skips.** Any key ends the film that is playing; **Alt ends all three.** One reads a key held down, the other sets a latch that nothing ever clears. It is a small thing, but it shows the style of the whole engine: behaviour lives in a few lines of plain code, and every one of those lines matters.

## What this means for the rest of the book

Everything that follows happens inside one pass around Figure 2. The scripts run first, then the bodies move, then the scene objects play, then the frame is drawn, all on one thread. (There is one exception: while a line of dialogue plays, its voice and facial animation are streamed out of the file by a multimedia-timer callback, which Windows runs beside the frame. The game's logic never runs there.) A script that needs to wait for something cannot block, because blocking would stop the entire game. How the engine waits without blocking is the subject of chapter 4, and it is one of the most elegant ideas in it.

## 3. Where the game lives

---

### The shipped tree

The data directory holds a dozen folders. Each belongs to one or two subsystems:

| Where each part of the game lives |                                                                              |                                 |
|-----------------------------------|------------------------------------------------------------------------------|---------------------------------|
| IAM/                              | archives: areas, scenes, world scripts, conversations, interface text, saves | the VM, the world, dialogue, UI |
| MESHES/                           | .3DO models and sets, .3DT textures                                          | the renderer, collision         |
| SCPTDATA/                         | .SCX scene scripts, .3DA clips, .3DP paths, .SFX sound tables                | scene objects, cutscenes        |
| MORPH/                            | .3DM: a line's facial animation WITH its voice                               | conversations, audio            |
| .CTL / .ani                       | the bodies' state graphs and their clips                                     | the actor runtime               |
| FONTS/ I2D/ IMAGES/ MAP2D/        | fonts, sprite sheets, bitmaps, maps (and the gunmen's nav grid)              | the interface, shoot mode       |
| TRACKS/ SOUNDS/ VOICEOFF/         | music, effects, narration                                                    | the sound bank                  |
| FLIS/                             | three MPEG-1 films                                                           | boot                            |

Figure 3 — The data folders, what they hold, and which part of the machine reads them.

The most important is `IAM/`, 67 files. Most of them are **archives**: one file holding hundreds of numbered chunks behind a directory at its start. `IAM\AREA` holds the places. `IAM\SCENE` holds the scene layers. `IAM\DIALOG` holds the conversations. `IAM\GLOBAL` holds the scripts that apply everywhere. The interface text and the saved games are in `IAM\` too.

### Plain formats

The whole project was possible largely because the formats are **plain**. Nothing is encrypted, there is no versioning beyond one field, and the little packing there is (textures are LZ-packed unless an image is exactly 64 KB; the audio is ADPCM) is simple and decodes exactly. A record is a C struct written to disk, an array is an array, and its count is usually right there beside it. A texture is a palette followed by indices. A mesh is a list of records of fixed size, 140, 32, 28, 32 and 52 bytes for its five kinds of record.

This was normal in 1999. Loading was mostly a matter of reading a file into memory and fixing up the pointers inside it. It explains a style you will see again and again in the engine: a structure read from disk is the structure the engine uses at run time. Some fields in a file are placeholders that the loader overwrites the moment it reads them (a texture's slot number, for instance, ships as `-1` in every one of the 2 534 materials), because on disk they have no meaning yet.

**From Unity:** there is no asset database and no import step. What Unity does once in the editor (convert, compress, build atlases) Omikron's tools did offline, and what shipped is already the runtime layout, closer to a memory dump than to a `.prefab`.

## A file is often more than its name

Two examples, both found only by reading the code that uses the data:

- A `MAP2D` file is the map the player sees in the sneak, and **also** the navigation grid the gunmen walk by in shoot mode.
- A mesh flag that makes a distant skyline **shimmer** (its vertex colours oscillate on the frame clock) also marks the bed of a canal you can swim in.

Nothing in the data announces a double use like that. This is the first hint of a principle Part IV makes explicit: the data can tell you where to look, but only the code can tell you what a field is.

## Case, and a lesson from a console

One more property of the tree turned out to matter the moment the replica ran anywhere but Windows. **Windows 95 and 98 did not care about letter case in file names, and the game relied on that.** The executable asks for `FLIS\EID0S.mpg` while the disc ships `EID0S.MPG`. On macOS or Linux that is a missing file. The replica therefore opens every file through one class, `DataFs`, which resolves names without regard to case. It resolves all 2 367 files it is asked for under four different manglings of their paths.

The PS Vita port added a lesson of its own. A copy of the `IAM` archives made with an FTP client in *text* mode had its line endings "corrected", which silently damaged binary chunks. The symptom was an empty area where the game's first scene should have been. Binary data must be copied as binary, and a symptom that looks like an engine bug may be the copy.

## Byte order, and a lesson from a PowerPC

The game ran on x86, so every number in every file is stored **little-endian**, low byte first. Most of the replica's readers build their values byte by byte and never noticed. A handful copied four bytes straight into an integer, which is correct on x86 and on ARM and wrong on a big-endian processor. When the replica was built for a PowerPC Mac (chapter 14), those reads found **no actors** where 1 032 should have been, 16 map lines of 79, and a traffic circuit that would not load. Nothing failed to parse: the numbers were simply other numbers. Every such read now goes through one helper that assembles the bytes in order, and every tool the checks run gives the same output on the PowerPC as on the Mac.

## **Part II — How the world behaves**

## 4. A tiny computer inside the game

---

### Bytecode

When you walk into a doorway in Omikron, a script runs. It is **bytecode**: one byte names the instruction, and its operands follow. A table compiled into the executable has 153 entries, each a pair: the address of the handler function, and how many operand bytes the instruction takes. The interpreter reads a byte, looks it up, calls the handler, and advances past the operands.

There are **5 785** such scripts in the shipped game, and between them they say almost everything the game does: *this conversation starts here, this door opens, this camera watches, this variable is now 1, this gunman patrols that corridor.*

The instruction set is small and specific. Here are a few of its opcodes, with the names this project gave them (the original's names were not shipped):

|                |            |                                              |
|----------------|------------|----------------------------------------------|
| dialog.start   | 272        | start conversation 272                       |
| ui.open        | 29, -1, -> | variable 19 open screen 29, store its answer |
| camera.set     | 2148       | cut to camera 2148                           |
| scene.load     | 237, 57    | load scene 57 over area 237                  |
| music.play     | 15         | play TRACKS\15.ADP                           |
| render.grey.on |            | switch the scene renderer to greyscale       |

The last one is a nice surprise. Opcodes 150 and 151 swap the whole scene renderer to a second, greyscale version and back, and every use of them brackets a run of camera instructions. So the game has **black-and-white cutscenes**, switched on by the script that plays them.

**From Unity:** a script here is closer to a coroutine than to a MonoBehaviour. It has no `Update()`. It runs from its first instruction until it has to wait for something, and it resumes exactly where it stopped. How it "waits" without `yield return` is the next section.

### How a script waits

This is the idea to take away from the chapter.

The whole game is one loop with no threads (chapter 2). So a script that opens a menu, or starts a fight, or waits for a character to finish walking, **must not block**: blocking would freeze everything, including the menu it is waiting for.

Instead, each running script, called a **context**, has a **status word**. The interpreter runs a context only while its status is 1:

```
while (ctx->status == 1)
    execute_one_instruction(ctx);
```

An instruction that has to wait simply writes a different number into its own context's status word and returns. The interpreter loop sees the status is no longer 1, and stops running that script. Its program counter and its stack are untouched. The script is **parked**.




Figure 4 — A script parks by writing its own status; the event that answers it writes 1 back.

Later, whatever it was waiting for happens (the screen closes with an answer, the fight ends, the camera move finishes) and the code that handles that event writes 1 back into the status word. On the next pass the interpreter runs the script again, from the next instruction. **Nothing polls**. Every resume is an event.

The status numbers name what the script is waiting for: 3 for a fight, 4 for a scene object or a player move, 6 for a screen, 7 for a camera move, and 8 to 11 for the stages of an area transition. One value, 5, is used for a transition that a second transition has overtaken, and nothing in the whole executable ever resumes it. That is not a gap in the reading. It is the original's own shape: such a script is parked for good.

This design is why a conversation can interrupt a cutscene, why an area transition can take three seconds of streaming without the game stopping, and why the engine's logic never needed a thread.

## A script belongs to a place

Scripts are stored inside the places they belong to, and they name things (scene objects, cameras) by small numbers that are **local to that place**. Object 12 in one scene is not object 12 in another. Because two places are loaded at once (chapter 5), a script must always be read against the place it came from. An early search for "which scripts start the Impasse's cutscene" found eight candidates across the corpus. Every one of them was another scene addressing its own object 12, and the real answer was zero: that cutscene is started by something else entirely, the scene's *startup script*, which the next chapter introduces.

## How the game starts talking to you

You can now follow the first minute of a new game with the real mechanism.

1. The frame loop loads the starting area, number 118, "Introduction Kay'l".
2. Loading a place **starts its startup script**. Nothing needs to name it; arriving is the trigger.
3. That script reaches `ui.open(29, ...)`, which opens the start menu and parks the script at status 6.
4. You type a name and confirm. The screen's answer is written into variable 19 and the context's status goes back to 1.
5. The script carries on and reaches `dialog.start 272`: Kay'l's first conversation.

The replica does exactly this, with nothing wired by hand, and its record of what the scripts did matches a capture of the original game, event for event: 42 of 42 in order. Part IV explains how a capture of the 1999 executable was possible at all.

## 5. Places

---

### A place is a chunk

The world is a set of **places**, and a place is a chunk in an archive. An area chunk carries its set, its characters, its props, its scripts, its shop stock and its trigger zones. A scene chunk, loaded over an area, carries the material for a moment of the story: which objects appear, what they do, which cameras film them.

Four ideas carry the whole subject.

### 1. A place runs a script the moment it loads

A chunk's offset `+4` holds its startup script. The loader hands it to a new context and queues it as soon as the chunk arrives. 173 of the 330 area and scene chunks carry one, and all 173 disassemble cleanly. This is what starts a new game (chapter 4), and it is also what orders a cutscene's beats: the Impasse cutscene's sixteen beats are fired, in order, by its scene's startup script, which then hands over with `scene.load(237, 57)`.

That fact stayed hidden for a while, and the reason is instructive. Every search for "who starts these beats" enumerated the scripts found in the trigger zones and the message subscriptions, 5 785 of them, and none of them did. The search was correct. The *inventory* was incomplete: startup scripts were not in it. A negative result is only as strong as the list it searched.


### 2. Everything else is a trigger zone

A **zone** is a quad on the floor, plus an arc saying which way you have to be facing, plus up to three scripts: one for entering, one for pressing the action button inside it, one for leaving. There are 4 558 of them. Each has one bit in the saved game, which is how a one-shot event stays shot.

**From Unity:** a zone is a trigger collider with `OnTriggerEnter`, `OnTriggerExit` and an "interact" event, except that the three handlers are bytecode stored in the level, and the "has this fired?" flag is part of the save file rather than of the object.

### 3. Two places are loaded at once

When you walk out of a street into a building, the street is not thrown away. It stays resident in the second of two **slots**, its animations still running. Walking back is not a reload.



*hidden is not unloaded - and it shares the 58-slot texture cache with the active one*

*Figure 5 — The active slot is drawn; the hidden one is not, but it is still loaded and still solid.*

## 4. Hidden is not gone

A place that is loaded but not shown is **still solid**. Its walls still stop you, and a step onto its floor is undone. One building in the game is laid out around that property.

It has a subtler consequence too, in the texture cache. The engine hands out 58 texture slots from one global pool and matches textures by **file name alone**. When a new set loads while the old one is still resident, a texture with the same name is taken from what is already in memory, even if the new set's copy of that file has different pixels. 182 texture names ship with different pixels in different sets. So some Anekbah signs genuinely draw a little differently depending on which neighbouring place you walked in from. The port reproduces that, because the original did it. It is one of several places in this book where being faithful means reproducing a quirk.

## State that survives

Everything the story remembers lives in one block of **8 192 bytes**: the variables scripts set, the zone bits, the inventory, the player's record. A new game starts from a template, `IAM\START`, which is itself just a saved game with no scripts in it. The save file stores the same block, plus the settings: saving a game also saves your options. A save costs one ring, *anneau*. (What happens when you have none is one of the places where the records still disagree with each other, and the manual lists it as open.)

## 6. Bodies

### A character is a tree of meshes

A character model (`.3D0`) is a hierarchy of meshes: a pelvis, a chest, the upper and lower arms and legs, a head, each parented to another by an ID. The **pelvis is the root** in all 181 character models. An animation clip (`.ani`, or `.3DA` for a scene's own clips) stores one rotation per mesh per frame as a quaternion, plus a root track for movement. Posing a body means walking the tree, composing each mesh's rotation with its parent's, and transforming its vertices.

One detail catches everyone: **key 0 of a track is a rest pose, not frame 0**. A clip of  $N$  frames holds  $N + 1$  keys. Read key 0 as the first frame and every loop shows a one-frame T-pose.

**From Unity:** this is a skinned mesh, except that each vertex belongs to exactly one bone. It is rigid skinning, with no weights. A body is a hierarchy of GameObjects each carrying its own piece of mesh, and a clip is an AnimationClip of local rotations. There is no blending tree beyond a short cross-fade.

### A body's behaviour is a state graph

Every character, the one you steer and the ones you do not, is driven by the same machine: a **state graph that shipped on the disc**, a `.CTL` file. Each state names an animation. Each transition names the **input bits** that take it. Press forward, and the graph moves from standing to walking, because an author drew that edge. Press the action button next to an object and it walks a chain of states: an adjusting step into position, a reach, a stand-up with the object in hand, a wait, and then, on your next press, into the bag or cancelled.




Figure 6 — A state graph (illustrative: `H_STAND` and the take chain, from `todo/take-animation.md`, are real; the walk and run states are drawn for the idea).

The input is **fourteen bits**, one word shared with the interface. Which key sets which bit depends on the context. There are four control schemes (adventure, swimming, shooting, fighting), each binding 14 actions on three devices. Entering a fight installs the fight scheme, entering shoot mode the shoot scheme.

This makes something that looks complicated turn out simple. "The player draws a gun", "the player dives" and "the player takes a step" are the same kind of event. The fight and shoot modes are not separate engines. They are different input schemes feeding the same graph, and different things pressing the buttons.

**From Unity:** a `.CTL` is an Animator Controller in which every transition condition is a bit mask over the input word, and in which the states carry gameplay data too: a hit's damage, a window in which it can be cancelled, a sound to play on a given frame, a "special move" to call.

## Who presses the buttons

In a **fight**, the opponent's AI presses combinations of bits into *his own input queue*, exactly as your keyboard presses into yours. Its behaviour comes from a profile in the `.CTL`: lists of button combinations, each with a percentage it rolls against and a waiting time. Harder levels wait less. The fight's difficulty is adaptive: the scripts raise the AI level when the last fight cost you under 30 life, and lower it when it cost 70 or more.

In **shoot mode**, each gunman has a small brain picked by character type, and it walks the level's navigation grid, the same `MAP2D` file the player sees as a map.

## The walker

Around the graph sits a **walker** that decides whether a step is possible: a slope steeper than 30° is a wall, a ledge up to 30 cm can be climbed, a fall is sorted into tiers by height. It knows when the floor is water, which puts the body into the swimming state. A jump is a clip whose forward motion (2.5 m) and flight time come from the animation itself.

The state numbers the engine keeps for a body, `ACTOR_STATE` 0 to 17, name these conditions: 14 is water; 7 and 8 are mounting and riding the slider, the game's flying car.

## The crowd

A city's crowd is not a set of placed characters. It is a **traffic circuit**, a `.OPT` file of lanes, routes and junctions. When an area loads, the engine walks along every pedestrian lane and places a walker at regular intervals, with the spacing set by the street-activity option (0 to 4) and a value from the circuit's header:

```
one walker every 39 × (5 - density) × h[3] units of lane
```

At the highest setting walkers are `39 × h[3]` apart; at the lowest, five times sparser. The walkers follow their lanes, overtake, wait for one another at shared junctions, and push the player aside with a simple sphere test. Vehicles, sliders and motorbikes, use the same circuit's vehicle lanes.



*The running example: Kay'l in Anekbah's main street with the crowd, the set's lights, the blob shadows and the dither, drawn by the port (`manual/images/anekbah-street.png`, with the command that made it in that folder's README).*

This matters later, in Part V. The port's crowd is **exactly the original's crowd**: the same rule, the same circuit, the same models. When the port was slow on a handheld, it was not because it drew more people than the game did in 1999.

## 7. Stories: conversations and cutscenes

---

### A conversation is a little graph

Each node of a conversation is a line somebody says. It has up to four **conditions**, evaluated to decide whether a reply is offered, and up to four **actions**, executed when you pick it. The two sets were told apart only by following the code: one event handler *evaluates* the first four pointers for a value while the reply menu is built; another *executes* the second four when you choose.

A line's text, its voice recording and its facial animation ship together: the `.3DM` file holds the face's animation **and** the ADPCM audio of the voice. A conversation also carries **its own cameras**.

There is one open mystery here worth knowing about. 105 of the 321 conversations have no way to be started: no script anywhere starts them. The likeliest reading is that they were **cut late**. Their text is as complete as the rest, but only 14% of them have the expensive facial animation, against 68% of the ones that are used.

### A cutscene is not a separate system

A cutscene is the ordinary scene machinery. A scene chunk's startup script starts a sequence of **objects**. Each object is a little program of steps: play this clip, move along this path, play this sound. Some objects have a **camera editing** attached, a recorded camera move that takes over the view while the object plays.

A program's steps can be linked into **sync chains**, so that a sound starts exactly when a clip reaches a given frame, or two steps run together. And a body placed by a scene is placed along an authored `.3DP` path, not at the position stored in its clip, which is a detail that took several wrong attempts to settle.

### Rules learned the hard way

- **A shot is as long as its editing**, not as long as the animation inside it.
- **When an editing ends, the camera does not go anywhere**. It holds its last frame until the next beat takes it.
- **A spoken line changes a character's pose, never their position**. Nor does anything else during a conversation: a body in the dialogue states plays its clip but is not moved by it, even one caught mid-stride.
- **A conversation's camera eases; a script's does not**. A dialogue camera's move speeds up and slows down along a curve. Every one of the 1 019 camera moves the scripts wait on asks for the linear curve, and all of them advance on `dt`, so a move lasts the same time whatever the frame rate: the title sequence's 23 moves stay on its music.
- **Not everything that waits is a cutscene**. A door sliding open parks a script exactly like a cutscene beat, and does not take away your control. What takes it away is the engine's own

*hold*, and the black bars at the top and bottom of the screen mean exactly that: *you are not in control right now*.

**From Unity:** a camera editing is a Timeline track driving a Cinemachine virtual camera; an object's program is a small Timeline of its own; and the startup script is the PlayableDirector that starts them. The difference is that everything, including when the camera stops, follows from a few engine rules rather than from what the author dragged onto a track.

## **Part III — Pictures and sound**

## 8. Drawing a frame in 1999

---

### Fixed function, and the CPU does the geometry

If you learned OpenGL after 2008, the first surprise is how little the GPU did. The original draws through **Direct3D in its 1999 fixed-function form**. It hands the driver vertices that are **already transformed and already lit** (D3DTLVERTEX: a screen position, a depth, a reciprocal  $w$ , a colour and a texture coordinate), plus a texture, and the driver fills triangles. There are no shaders. Every vertex of every character is posed and projected **by the CPU**, on a Pentium II.

**From OpenGL:** imagine a vertex shader that does nothing but pass through `gl_Position` computed on the CPU, and a fragment shader that does `texture * colour`. The lighting, the skinning and the projection all happened before the driver saw the data.

### Which meshes are drawn

A set is a few thousand meshes. Each carries a word of flags, and the engine's decision "is this mesh drawable?" is a single test:

```
if (mesh.flags & 0x800043) skip;
```

That one mask replaced three heuristics the project's own viewers had used before the engine's rule was read, and it disagreed with them in both directions. It is a good example of why reading the code beats reasoning about the data.


Then a **visible-set walk** culls meshes against the camera's frustum: a distance test, then the four side planes, each against the mesh's bounding sphere. It culls whole meshes, not triangles, which is cheap. (The port at first left the side planes out, on the grounds that a wrong plane sign deletes the world silently. Put back, they halve the set runs a street frame draws.)

Then, triangle by triangle, the CPU drops every face it sees **from behind**: a cross product of the projected corners decides, and only a mesh flagged two-sided (93 of 16 188, nearly all water) escapes it. The device itself is told not to cull, and for a month this project read that render state as "the engine never culls". The port drew the back of the scenery, and dialogue cameras authored behind a wall looked blocked. The cull was one level up, in the engine's own submit, before anything reached the device.

### The draw order is a number

This is the mechanism that decides almost everything about the picture.

Every triangle that survives is put into one of **16 384 buckets**, chosen by a **14-bit key**. The key's low six bits are the **texture slot**, and nothing else chooses the texture. The bits above come from the mesh's flags: blended or not, cutout or not, and so on. At the end of the frame, `Render_FlushBuckets` walks the keys from 0 to 16 383 in **ascending** order and draws each non-empty bucket.



*Figure 7 — The draw order is the bucket key, ascending.*

Three consequences follow from that one design.

- **State changes are cheap.** All the triangles sharing a blend mode and a texture are drawn together. Nobody had to write a state cache: the order itself minimises the changes.
- **Transparency works.** Blended geometry sets a high key bit, lands at the top of the range, and is drawn after everything opaque.
- **Coincident faces are settled.** When two faces occupy exactly the same place, the one with the lower key is drawn first. The depth test is strict (a pixel is replaced only by something strictly nearer), so the first-drawn face keeps every pixel. Chapter 14 comes back to this, because it turned out to be one of the hardest things for a modern GPU to reproduce. (The shop signs in Anekbah look like the textbook case: the two sides of a sign are the same four vertices, each with its own advert. They are not one. The two sides are wound opposite ways, so the back-face test above keeps exactly the side that faces you, and the two never compete.)

**From Unity:** the bucket key is a render queue plus a sort key. It is roughly what URP does when it sorts opaque objects by material to batch them, and draws transparent ones afterwards, except that here the sort is a fixed integer order with no camera-distance sort at all.

## Textures: 58 slots

Textures are paletted: each texel is an 8-bit index into a 256-colour palette. The loader hands out **58** texture slots from one global pool, matching a texture by its **file name** alone, and on a match reuses

what is already in memory. That is the cache chapter 5 described, whose side effect is that a set can draw its neighbour's version of a texture.

## Colour is baked

A set is **pre-lit**. Every vertex carries a colour baked into the file, and that colour is what reaches the screen: the driver is told the vertex has a diffuse colour, so it is a colour, not a brightness. (The project's early viewers read only the green byte, which drew every set in grey. 39% of set vertices are not grey.)

The moving population, the crowd and the characters, is lit at run time, per vertex, by a small table of **lights** that ships inside each set's model: 4 179 of them across 216 models, each with two radii, a colour and a position. A vertex takes  $-(N \cdot L)$  through a linear falloff and an integer colour ramp.

## The picture's particular look

The engine sets its render states deliberately, and they are part of the game's look:

- anti-aliasing **off**;
- textures filtered **bilinear** on a 3D card, sampled **point** on the software devices, and **no mipmaps** on either;
- the driver's **dither on**;
- fog **linear**, and **black**;
- the sky a **flat painted ceiling** that follows the camera, not a dome;
- a far skyline that **shimmers**: a 32-byte table oscillates the vertex colour of 233 set meshes on the frame clock.

A replica has to do all of them, including the dither and the shimmer, which are easy to leave out because they look like defects. They are the original.

## Shadows are blobs

A character's shadow is not a shadow pass. It is **one soft quad**, copied under a handful of bones (the chest always, the head and legs from detail level 1, the arms at level 2) and faded by distance to the floor below each bone. The floor is found by probing straight down, the same kind of probe the walker uses.

## Mirrors are a second pass

Six meshes in the whole game are mirrors. When one is visible, the engine **reflects the camera** through the mirror's plane and draws the whole scene a second time, with the screen flipped horizontally. It is the most expensive thing the renderer ever does, and it is used sparingly.

There is no stencil, and nothing marks out the mirror's shape. The reflected pass is drawn **first**, and the real one over it with nothing cleared in between. The reflected pass leaves behind the depths of a

virtual room beyond the glass, and the real room's nearer walls cover it everywhere except through the mirror's opening. Draw order and depth do all of it.

## The interface is a different world

The 2D interface does not go through the 3D path at all. It is a **16-layer display list** of rectangles, sprites and text, blitted with a colour key. A blit is a memory copy. That is why the port can reproduce the interface **pixel for pixel**, while it cannot do that for the 3D half (Part IV explains what it does instead).

## A captured frame, and the port's



*The original engine's framebuffer: Kay'l's apartment through dialogue 402's camera, letterboxed, with Telis and a subtitle (traces/frames/dlg402-47.png).*



*The same set through the same camera, drawn by the port's software rasterizer, without the characters and the text ([manual/images/dlg402-port-render.png](#)). This pair is how the 3D path is judged: by edges and coverage against a chance floor, not pixel by pixel (chapter 11).*

## RGB565

The framebuffer is **16-bit**, five bits of red, six of green, five of blue. That shapes what a comparison against a captured frame can mean. A capture comes back as 8-bit values, but those are the host's expansion of the original's 16-bit pixels, not the game's data. So every comparison in this project is made in **565**.

## 9. Sound without a mixer

---

### The mixer that isn't there

The most useful thing to know about the game's audio is that **there is no mixer in it**. The engine opens one DirectSound primary buffer, sets it to 22 050 Hz stereo, and starts it looping. After that, every sound is a *secondary* buffer that DirectSound itself sums. Nothing in the executable ever adds two samples together.

What the engine does is **decide**: which of its 160 buffers to use, which of its 16 voices plays it, where it is in the world, how loud it is, when it stops. The listener is told that the world's unit is an **inch**. The volume law is an **attenuation**, 0 for full and 100 for silent.

That changes what a port can claim. The decisions are portable and checkable. The sound that comes out is the operating system's, and nothing in this project records audio, so the exact attenuation curve and panning have **no reachable evidence at all**. They are implemented as honest approximations and written down as unverifiable, not presented as established.

### One decoder, exact

Speech, music and the facial animation's audio are stored in a variant of **IMA ADPCM**: four bits a sample, each nibble adjusting a predictor by a step that grows or shrinks. It differs from the textbook version in two ways, and both matter: the high nibble is decoded first, and the textbook's small rounding term is absent. Leave the term in and the signal drifts by thousands of units over a line.

The port's decoder is **sample-identical** to an independent one across all 777 files that carry a voice, 225 million samples. In 2026-09 it also became a **table**: a channel's state is just its predictor and its index, so each nibble's effect can be precomputed,  $89 \times 16$  entries. It was proven identical over all 93 million states a channel can be in.

### Music as a stream

A music track is a stream of stereo ADPCM at 22 050 Hz. The port first decoded a whole track when it started playing: simple, and 16 MB of memory per track. That was fine on a Mac and was refused by the PS Vita's heap the moment a city loaded. So the port now decodes **as it plays**, from the open file, keeping about a second queued in the device and topping it up a quarter of a second at a time.

# 10. The interface

---

## Screens are data, mostly

The game's menus are data too. There are **37 screens**: the start menu, the options, the save and load panels, the shops, the terminals, the lift, a few puzzles, and the sneak. Each is a row in a table compiled into the executable, naming its background bitmap, its text file, and the callbacks that open and close it.

What a screen contains is a **tree**: a screen owns a panel, a panel owns up to ten lists, a list owns items, and an item is 72 bytes saying where it sits, what it draws and which flags it has.

**From Unity:** a panel is a Canvas, a list is a layout group, an item is a UI element, and the "button hook" is an `onClick` pointing at native code. The difference is that the whole tree lives in the executable's data section, so it had to be lifted out to JSON: no data file carries it.

## The code a table points at

What makes a screen *work* is not in the tree but in small native functions it points at: a list's input hook, an item's draw hook, the callback a button press runs. Many of them are **called from nowhere but a table**. The disassembler that produced this project's listing only recognises code where it sees a call, so 26 of the 30 per-screen open and close callbacks were not recognised as functions at all. Each screen the port brought up meant finding them in the raw image first. Part IV comes back to that trap.

## Text

Text is drawn with the game's own **13 fonts** (2 899 glyphs, each pixel a coverage value 0..31 into a colour ramp), laid out by the engine's own block layout, with a small markup language for colour, font and images. The start menu in the game's invented alphabet is drawn by the port's text code, from the same fonts, and matches the original's framebuffer pixel for pixel.



*The start menu's four labels drawn by the port from the game's own fonts: 6 132 pixels, each the same as in the original's capture shown in chapter 2 ([manual/images/menu-text-port.png](#)).*

## Input is shared

The interface reads the same **14-bit input word** as the bodies do (chapter 6). A menu and a character are listening to the same word. Confirm, back and close are three of its bits.

# Interlude — one frame in Anekbah

---

Part III ends the description of the original engine. Before turning to how it was read and rebuilt, it is worth putting the pieces together once, on the running example. You are standing in Anekbah's main street. You press *forward*. Here is what one frame of the game does with that, in order, with the chapter that explains each step.

**The clock** (chapter 2). The message pump has nothing to do, so the frame runs. The machine is keeping up, so `dt = 30 / fps` comes out at about 1.0: one thirtieth of a second of game time.

**The input** (chapter 6). The keyboard is read through the adventure scheme's bindings, and *forward* sets one of the fourteen bits in the input word. Nothing else sees the key.

**The scripts** (chapter 4). The frame first runs every live script context. In a quiet street almost all of them are parked, waiting for a zone, a screen or a message, so almost nothing executes. The port measured it: about fifty instructions in 150 frames. If your step carries you into a trigger zone, its *enter* script is queued, and it will run from its first instruction.

**Your body** (chapter 6). Your state graph is in `H_STAND`. One of its edges names the *forward* bit, so the channel takes it and the body starts the walk clip. The walker then asks whether the step is possible: it probes the floor under the new position, checks the slope is under 30° and any rise under 30 cm, and sweeps the body's spheres against the walls.

**The crowd** (chapter 6). Every walker spawned along the street's lanes takes its own step along its route. One slows because another is ahead of it at a shared junction. One brushes past you, and the push test nudges you aside.

**The scene** (chapter 7). Scene objects with running programs advance their steps, and a crane's cargo swings along its path. The camera follows you, since no editing is holding it.

**The draw** (chapter 8). The visible-set walk culls the set's meshes against the frustum, and every triangle seen from behind is dropped. Every surviving triangle goes into a bucket by its 14-bit key: the street's opaque walls and floors into the low buckets texture by texture, the lamp's additive glow near the top. The crowd and you are posed on the CPU, and lit per vertex by the lights the set's model carries. Under each body, a soft shadow quad is copied beneath its chest, and beneath its head, legs and arms depending on the detail setting, faded by how far the floor is below each bone. The far skyline's vertex colours shimmer on the frame clock. `Render_FlushBuckets` walks the keys upward. On the shop sign on the wall, the two sides of the panel share one position, but only the side facing you survived the back-face test, so its advert is the one you see. The frame goes out dithered to 16 bits.

**The sound** (chapter 9). The engine decides which of its voices play your footsteps, triggered on a frame of the walk clip, and how loud the street's ambience is from where you stand. DirectSound mixes.

**The interface** (chapter 10). No screen is open, so the 2D display list has little to add; it is walked over the picture all the same, layer by layer.

Then the pump goes idle again, and in a thirtieth of a second it all happens once more.

Every step in that list was once a question, answered by reading a function in the executable. The next part is about how that reading was done, and how anyone can tell whether it was done right.

## Part IV — Reading a binary

# 11. How you read an engine without its source

---

## What you start with

The project began with the shipped game and a **decompilation** of its executable: a disassembly listing and C-like pseudocode generated by a decompiler (Hex-Rays). That pseudocode is a machine's guess at what the assembly does. Variables are called `v17`, functions `sub_449750`, structures are raw offsets from a pointer. It is far better than nothing, and it lies in small ways all the time.

Everything in the first ten chapters of this book was recovered from that material. This chapter is about *how*, because the method is what makes the findings trustworthy, and because it transfers to any engine you might want to read.

## The data finds, the code confirms

The rule is short: **use the data to find things; use the code to confirm them.**

Reading the bytes is fast and legitimate for forming a hypothesis. The 68-byte trigger-zone record was found by locating every offset in a chunk that disassembles cleanly as bytecode and looking at the gaps between the fields that point at them. The table of actors was noticed because it contained strings that looked like model names.

What is not allowed is stopping there. A layout is not established until a **loader in the executable** says so, because a wrong layout that happens to fit the shipped bytes looks exactly like a right one. The project kept a list of the times this bit:

| what the data suggested                                       | what the code said                                                                  |
|---------------------------------------------------------------|-------------------------------------------------------------------------------------|
| a scene's object count was a 32-bit integer                   | the loader reads 16 bits: 22 of 71 chunks had been silently rejected                |
| <code>IAM\GLOBAL</code> parsed plausibly as an archive        | the loader opens it as a plain file with a fixed header                             |
| the trailing fields of a <code>.CTL</code> were dead pointers | the loader never follows them; it recomputes them                                   |
| a 276-byte array held no bytecode, so it was not interesting  | it was the table of actors, the whole link from a conversation to a character model |

The last two are the shape to watch for. "These pointers are garbage" and "these aren't scripts" were true statements about a hypothesis, and false statements about the field.

## Make the parse able to fail

A parser that "decodes without crashing" has proven nothing. Random bytes decode. So every reader in the project is built to be able to **fail**:

- the walk through a file must land **exactly** on the file's size;
- a shared pool must be consumed **in order, with no gaps**;
- every cross-reference must resolve (the .CTL graphs have 2 044 edges, and 0 are unresolved);
- every animation quaternion must be of unit length (243 362 of 243 362);
- two independent chains must agree (a conversation's character found through the actor table, and through the face mesh's vertex count, agree 150 times in 153).

The best checks look at the *shape* of an accumulation, not just its total. Two per-frame 3-float tracks were once both read as movement deltas. One was refuted, because integrating it walked every character off the map forever. The other was confirmed, because its integral **converges**: Kay's position climbs over forty frames and then sits still for the remaining 230, which is a man walking in and stopping.

## When the reading itself is in doubt

Sometimes the code has decided, and the only question is whether a tool read it correctly. Then the data can arbitrate between two candidate readings.

The operand lengths of the 153 opcodes are the example. Recovering them from the handlers' assembly gave 21 disagreements with the table. Applying all 21 made the corpus decode worse. Applying them one at a time showed that 6 were real. And a length later "confirmed wrong" by the corpus (op 103) turned out right once three *other* lengths had been fixed: a test of one value while others are wrong tests all of them at once.

## The traps are in the tools

A surprising share of the wrong turns came from the tools, not the game:

- **Code nobody calls is not recognised as code.** The decompiler makes a function where it sees a call instruction. A callback that only ever appears as an address in a data table is not recognised at all, and a tool that looks it up by label silently returns the *next* function instead.
- **A name is a hypothesis.** One function was named `Perso_SetInputEnabled` because it looked like it; its argument actually **blocks** input. The port trusted the name and the player's action button went dead after the first conversation.
- **A value in 4096ths of a turn reads plausibly as degrees.**
- **A render state is not the picture.** The device was told not to cull, so "the engine never culls" was written down; the engine had culled back faces in its own code first. The block that set point sampling was read as the game's look; it was the arm for *software* devices, and a 3D card took the other arm, which filters. Both times the state was read correctly and attributed wrongly. Read what reaches the device, and which device.
- **A check that reads a log line** reports what the code *intended*, not what it produced. A line printed as a string literal cannot fail.

## An oracle: the game narrates itself

For a long time the project could only compare itself with itself, and a wrong reading applied consistently passes every such test. What changed that was a discovery about the original: **every script instruction announces its operand** through a Windows API call (`GetPrivateProfileStringA` on a `.TAG` file), and that call sits *before* the check for whether the debug window exists. So the unmodified 1999 executable, run under CrossOver on a Mac, can be made to say what it is doing, with no patch, no shim and no debugger.

Those logs are the **golden traces**. The replica's record of what the scripts did is compared against them event for event. The same rig captures the original's **framebuffer**, which gives a pixel oracle for the interface, and a silhouette-and-coverage oracle for the 3D view, where the driver's own rasterisation makes per-pixel comparison meaningless.

## How much a green check is worth

Every claim in the project carries a **grade**, from the six tiers of `docs/PORTING.md`:




Figure 8 — The six tiers of evidence. Only 1, 2 and 4 can catch a wrong reading applied consistently.

Tier 3, agreement with a second implementation, deserves its warning: **two implementations of one reading agreeing is not evidence**. It catches typos and off-by-ones. It cannot catch a misunderstanding, because both copies were written from it.

And every check must be **shown to fail**: break the code on purpose and watch the check go red. It is the rule that earned the most in practice. A check that stays green when its subject is broken is not a check. Chapter 15 has a fresh example: a fix was committed on the strength of four "agreeing" frame captures, the check written for it could not be made to fail, and that is what revealed that the four captures were all of the same first frame of a program that had stalled.

## And a person playing it

The last source of truth is the least technical. Most of the faults fixed in the port's recent history were found by **someone playing it**, often with the original running beside it. Some errors are invisible at rest. An angle that wraps from  $+359^\circ$  to  $0^\circ$  is the same rotation in a still frame, and a full turn the wrong way when the camera interpolates. A still frame and a test cannot see that. Watching can.


## Part V — Rebuilding it

## 12. The shape of the replica

### What it is

`engine/` is the replica: C++20, roughly 60 000 lines in the engine proper and 33 000 in the backends that draw and play it, and **no required dependency**. `make` on a machine with nothing installed builds every probe and passes the test suite. SDL and a Vulkan loader are optional; they buy you a window.

**The port: one engine, reference and live backends behind one boundary**



*the same shape for sound (PCM buffers vs a device) and input (a replayable stream vs a pad)*

Figure 9 — One engine; reference and live implementations behind one boundary.

The engine's directories follow the original's subsystems:

| directory                                                       | what it holds                                                                                                                                          |
|-----------------------------------------------------------------|--------------------------------------------------------------------------------------------------------------------------------------------------------|
| <code>formats/</code>                                           | one reader per file format                                                                                                                             |
| <code>script/</code>                                            | the <b>Session</b> (the resident places, the transitions, the frame), the VM's handlers, the zones, conversations, the game-state block, scene objects |
| <code>actor/</code>                                             | the <code>.CTL</code> channel, the player's controller and cameras, posing, the walker, the slider, melee, shoot mode, the crowd and its vehicles      |
| <code>o3de/</code>                                              | the bucket keys, the 58-slot texture cache, the visible-set walk, particles, the depth tie, collision                                                  |
| <code>ui/</code> , <code>audio/</code> ,<br><code>input/</code> | the interface, the sound decisions, the four control schemes                                                                                           |
| <code>platform/</code>                                          | <code>DataFs</code> (every file access, case-insensitively), boot, films, threads                                                                      |
| <code>app/</code>                                               | what a frontend needs and SDL does not: the command line, the game's state (no drawing in it), shared helpers                                          |

## The one design decision

Every output subsystem has a **reference implementation** and a **live one** behind **one boundary**:

|         | reference                                        | live                                                                                               |
|---------|--------------------------------------------------|----------------------------------------------------------------------------------------------------|
| picture | a software rasterizer into an RGB565 framebuffer | Vulkan (MoltenVK on macOS), GLES2 for the PS Vita, and fixed-function OpenGL 1.x for a PowerPC Mac |
| sound   | PCM buffers                                      | an audio device                                                                                    |
| input   | a replayable event stream                        | a keyboard, or a gamepad as the engine's joystick                                                  |

The reference is what the checks measure. The live one is what makes the replica playable. Neither may be required to build the other.

The renderer boundary is placed at the level of **decisions**, not API calls. The engine does not say "bind this texture, draw these vertices". It says "here is a draw: this bucket key, this range of this geometry, this blend, this cutout". A backend turns decisions into API calls, and never makes a decision itself.

```
begin(view)      the camera and its frustum
submit(draw)     { bucketKey, geometry, range, blend, cutout }
end()            the frame
```

Put the boundary at the API level instead, and the ported decisions, which are the thing that was actually reverse-engineered, would leak into Vulkan-specific code. A second backend would mean extracting them again. The boundary is what made four backends possible.

**From Unity:** it is the difference between writing game code against `Graphics.DrawMesh` and writing it against the Vulkan API. The engine speaks in draws and materials, and each backend is a render pipeline.

## Tables that are not in any file

Some of the game lives in the executable itself: the opcode table, the interface's widget tree, the key bindings, the special moves, the camera presets. A replica cannot read those out of the data directory, so they were **lifted to JSON** (`tables/`), each with a self-check that re-derives it from the executable and compares.

## Enhancements are off

A second rule sits beside the boundary: **anything the original did not do is an enhancement, and every enhancement is off by default**. Multisampling, mipmaps, real shadow maps, per-pixel light, supersampling, a 60 fps pacer, bodies smoothed between animation keys, text scaled with the screen: all exist, all behind a flag. (Bilinear texture filtering was on that list until it was read that the original's 3D-card device set it; it is now the default on every GPU backend.) A replica judged against the original must draw what the original drew unless told otherwise.

The flip side is just as important. Before building an enhancement, check whether the game already did the thing and the port had dropped it. The dither and the shimmer (chapter 8) were found that way: they looked like missing features and were missing *fidelity*.

# 13. Running the world

---

## The Session

The heart of the replica is the **Session**, in `script/area.cpp`. It holds the two resident place slots, runs the transitions between them, owns the script contexts, and advances one frame. It is the port's counterpart of the original's frame function, and it keeps the original's order: scripts, then bodies, then scene objects, then the camera, then the draw.

It is also where the evidence meets the code. The Session's record of which scripts ran and what they announced is what is compared against the golden traces. From a cold start, it reproduces the capture of the game's opening **42 of 42 events, in order**, with nothing wired by hand. The start menu, the name field and the first conversation all come out of AREA 118's own startup script.

## The frame loop of the viewer

`omk-play` is the playable frontend: SDL, a window, the pad, the audio device. It was once one `main` of over 21 000 lines. It is now a `PlayState` object whose `main` is 57 lines: the setup in sections, one turn of the loop in six phases (input, control, modes, world, screens, present), each phase in parts, and the GPU window in one file per backend, so that no game code carries a backend `#if`. The split was proven by a record of 28 scenes, each the same frame before and after. Each frame it asks the Session to step, poses the bodies, gathers the draws, and hands them to a backend.

It also carries its own instruments, and they are part of how the port is developed: a frame's cost is marked section by section, a slow frame prints what took the time, a `--dump` writes the framebuffer, and `--flicker` catches a fault too short to screenshot by watching for frames much darker than their neighbours. They sit behind one seam, so a build for players can leave them out (`INSTRUMENTS=0`).

## Determinism

A run limited by `--frames` uses a fixed step of exactly one engine frame, so the same command gives the same frames. That is what lets a check render a street, change one line of code, render it again and compare the two dumps byte for byte. Most of the speed work in the next two chapters was proven exactly that way: **same output, less time**.

# 14. Four renderers, and two faces in the same place

---

## The software rasterizer

The reference renderer is a CPU rasterizer into a  $640 \times 480$  RGB565 buffer, following the original's conventions (the right-handed world with **Y pointing down**, the bucket order, the strict depth test). It is what `verify.py` measures, and against the original's own captured framebuffer it reaches tier 4 for one camera: the apartment through dialogue 402's camera, compared by edge alignment and coverage against a chance floor, not pixel by pixel.

It is too slow to play the city. It does not need to be fast.

## Vulkan and GLES

The live renderers turn the same draws into GPU work. Vulkan, through MoltenVK on macOS, is the desktop one. GLES2 was written for the PS Vita, whose GPU is programmed through vitaGL, an OpenGL ES 2 layer. Both agree with the software reference on coverage, to 99% or better (Vulkan 0.995 through dialogue 402's camera; GLES 0.996 there and 0.992 on the street), which is the right measure for a GPU: a driver's rasterisation rules and rounding are its own.

They also filter. The original had two device set-ups: a 3D card got **bilinear** filtering, a software device **point** sampling. The live renderers stand where the card stood, so they filter by default; the software reference stands where the software device stood, so it does not. That agreement is measured with both on point sampling - the comparison is about which triangles land where, not how a texel is blended.

The GLES backend goes further than the original ever did. It **poses and lights the characters in its vertex shader**: the rest geometry stays on the GPU, and each frame sends only one matrix per mesh and the lights that reach the body. The original did all of that on the CPU. A handheld needs it, because what a Pentium II did for this game's bodies is a large part of a Cortex-A9's frame.

## A fourth, for a 1999 Mac

The fourth renderer answers a what-if: how would Omikron have looked ported to a Macintosh of its own day? Such a machine has no shaders and, in 1999, mostly no hardware transform either. So this backend uses **OpenGL 1.x fixed function** and does what the original did with Direct3D: one draw per bucket, a render state changed only when it differs, the texture chosen by the key's low six bits, 16-bit textures, the colour key as an alpha test, and the vertices transformed, clipped and culled **on the CPU**, with the fog computed per vertex. Doing the CPU's share by hand was faithful, and it was also forced: under emulation, the card's own transform let triangles that cross the near plane through as garbage, and its fog darkened the near scene.

It runs, cross-compiled, on Mac OS X 10.4 on PowerPC, in an emulator: the films, the menu and Anekbah's street at 6 to 10 frames per second, against about one for the software rasterizer on the same emulated machine. It agrees with the reference on coverage to 0.993. Getting there needed the byte-order fix of chapter 3, a big-endian build of every tool, and one more lesson about floating point: the PowerPC compiler fuses a multiply and an add into one instruction that rounds once, where the Mac rounds twice, and a 300-frame traffic run drifted by a tenth of a unit until fusion was turned off on both sides. The original, on an x87, had no fused operation at all.

Mac OS 9 itself has no SDL. So the viewer's game code now reaches the host (the window, the keys, the sound, the clocks) through **one interface**, the renderer boundary's counterpart for the host, and compiles without a single SDL header. A Carbon frontend will replace SDL by implementing that one class.

The engine underneath is already there. Built once as a Carbon program, the headless boot runs on Mac OS 9 and on Tiger, and what it decides is byte-identical to the Mac's. The last obstacle was the most instructive. A file stream crashed on start-up, but only in a large program: a small test passed, and the same test crashed as soon as about two megabytes of other code were linked beside it, the engine's or anyone's. The cause was in the toolchain. Its linker gave two of the C++ library's objects the same address, so the library's own locale set-up overwrote one of them. The engine now reads its files without C++ streams at all. The lesson is one Part IV would recognise: a test too small to reach the fault proves nothing about the program that does.


## Two faces in the same place

Chapter 8 said that when two faces occupy the same place, the first drawn keeps every pixel, from every angle, with no flicker. A strict depth test on a **quantised** depth buffer produces that: two faces at the same depth quantise to the same value, the second is not strictly nearer, and it loses every pixel. A later face wins only if it is nearer by a whole step of the buffer.

A GPU does not behave that way. Two faces that split the same quad along different diagonals have interpolated depths that differ in the last bits (about two parts in ten million), and the depth test picks per pixel wherever the noise falls. The result is **dots of the other face**, re-rolled by every sub-pixel camera move. Asking for a 16-bit depth buffer with the same strict test is not enough: a rounding boundary still falls inside the noise.

The port met this first on Anekbah's shop signs, and drew the wrong conclusion from them for three weeks. A sign's two sides are the same four vertices with an advert each, and they flickered in the port. The tie was blamed. The real cause was that the port drew the back of the sign at all: the original culls it (chapter 8), so its two sides never compete. Once the port culled too, Anekbah's competing faces fell from 248 to 87. But 87 is not zero. The rest are faces that really do share a place and a side, and they still need the original's answer.

## Two faces in the same place: the original's answer, a GPU's, and the port's



Pushed back by the engine's own band rather than removed, a loser that SEPARATES - a door's leaf swinging open - simply draws again: no per-frame watch, and no hybrid (bodies keep the per-frame tie). A shop sign's two sides are NOT such a pair: they wind opposite ways, and the back-face cull keeps one.

Figure 10 — Two coincident faces: the original, a GPU float compare, and the port's depth tie.

The port's first answer was the **depth tie**. Before a draw, it found faces whose positions an earlier depth-writing face already claimed, and **degenerated** them in the vertex buffer: their three corners collapsed to one point, so they drew nothing. The picture was the original's. The cost was a walk over the faces every frame, kept up to date for geometry that moves.

A great deal of work went into making that walk cheap, and a reader's question pointed past it: *the original has no flicker, so its answer must be cheap to reproduce*. The census that followed (Part IV's kind of check) seemed to block the easy version. 1 540 of the sets' coincident groups span two meshes, and the first examples are **the two leaves of a door**. Doors move. Open, the faces separate and the losing one must draw again. A loser removed once, at load, would stay missing while the door stood open, so a hybrid was argued: groups within one mesh answered at load, the rest watched every frame.

It was never built, because a closer look at what the original actually does made it unnecessary. The original does not *remove* the losing face. Its strict test on a quantised buffer only demands that a later face be nearer by a whole step. So the port now decides the losers **once per set**, from the set's whole draw order, and draws them **two 16-bit steps back** instead of degenerating them. A closed door's losing leaf stays hidden. An open door's leaf is far from its twin, the small push changes nothing, and it draws. No per-frame walk, no hybrid. The frames are byte-identical to the per-frame tie's over a walk past the signs, and the tie's share of a street frame (up to 4.4 ms on an M3, about 50 ms on the console) is gone for the set. Only posed bodies keep the per-frame tie.

# 15. Making it fast

---

## The yardstick

The original ran on a Pentium II. The port wants to run on a **PS Vita**: four ARM Cortex-A9 cores at 444 MHz, and a homebrew heap measured in hundreds of megabytes. The rule for the work is strict. **Nothing may change what is drawn or decided**: every step replaces *how* an answer is computed, never the answer, and its check is "same output, less time". A step that moves a pixel or a position is a bug in the step.

Timings in this chapter come from two different Macs (an M1 and, later, an M3). A millisecond from one is not comparable with a millisecond from the other, and the Vita is slower than both by a factor that was, for a long time, only estimated.

## The first profile: the port's own overheads

The first measurement, on the M1, found the largest cost in an unexpected place: the **shadows' ground probe**. The original probes straight down from each shadow bone, and the probe itself was faithful. What was not faithful was *how* the port answered it: by scanning every walkable triangle of the city, some 15 000, for each bone of each body, every frame. The original culls whole meshes first. A **spatial grid** over the walkable geometry took the street from 24 to 45 frames per second, with byte-identical frames.

That set the pattern for the whole effort. Almost every large cost was the **port's**, not the game's:

- linear scans where the original culled (the probe grids, the walker's sweeps);
- whole-set copies every frame when one crane moved (a per-mesh patch, then a list of exactly which corners changed);
- the depth tie rebuilding its tables from scratch;
- a round trip through the CPU for every frame's picture (the frame now stays on the GPU when nothing is drawn over it);
- memory held needlessly: the music decoded whole, textures held several times, sprite tables mostly empty.

## The handheld


Then the port ran on a real console, and the console had its own lessons. vitaGL copies a **whole buffer** when a small part of it is written while the GPU may still read it. The depth tie's three-vertex patches into a 5 MB set buffer turned into whole copies, and a city frame took 8.4 seconds. Writing through a mapped pointer fixed it. The log, written synchronously to the memory card one line at a time, fed the very lag it reported. The music's 16 MB was refused by the heap as a city loaded.

And the three levers the earlier analysis had named were pulled one by one:

- **Posing on several cores.** The crowd's bodies are independent, so they are posed on a thread pool, with the frame bit-identical either way. On the console, 2.7× on three workers.
- **Posing on the GPU.** The walkers and the staged bodies are skinned and lit in the vertex shader (chapter 14), and since 2026-09-30 the player too. On the console a GPU-posing self-test had quietly been switching it off: the Vita's shader compiler *rounds* when it converts to an integer, where the Mac's truncates, so every odd mesh took its even neighbour's matrix. Fixed, the city frame went from 110-124 ms to 59-70.
- **NEON.** Two hot loops got ARM vector versions beside the portable ones, each proven bit-identical.

## Fewer calls, fewer allocations

The next round looked at what the GPU backend and the heap were paying for.



*\* outside the software reference rasterizer, which the Vita never runs (1214 -> 651 in all)*

Figure 11 — The GL state calls and the heap allocations of a street frame, before and after (M3; counts, not milliseconds).

- The GLES backend set every piece of state on every draw. It now remembers what the last draw left: **1 809 state calls a frame became 92**, same frames. This is the modern counterpart of what the original's bucket order gave it for free (chapter 8).
- A street frame made about **720 heap allocations** outside the software rasterizer: scene programs building a list and a tree node on every tick, the light ramp rebuilt per light per body, per-frame maps of particles and moving meshes. It now makes about **160**, same frames.
- The music decoder became a table (chapter 9).

They were measured in counts on a Mac. The console log that followed is in the next section.

## A wrong turn worth telling

In the same round, a comparison showed a street frame 537 pixels different between two ways of uploading moving geometry. It looked like a bug in the faster path. It was not. The difference came from an experimental merge that assumed a list was sorted, and it was not. On the way there, a fix for a suspected clock problem was committed on the strength of four captures that agreed with each

other. The check written for it could not be made to fail, and that is what gave it away: the four runs had stalled at frame 0, because the display was asleep, and each had dumped the same first frame. The fix was reverted, and the lesson went into the project's list of traps: **a dump is evidence only with the frame count it came from**. Part IV's rule, that a check must be shown to fail, caught it.

## Doing it the original's way

The round after that took a different method. Instead of profiling the port and asking what was slow, it read, section by section, **how the original did the same job**, and asked why the port did more. The answers were nearly always that the original did less:

- **The view cull had four side planes** the port had left out. With them, half of a street's set runs and most of its walkers are not drawn at all.
- **The crowd has levels of detail**. The original picks a simpler skeleton by view depth, at 10, 20, 30 and 40 m. The port now does too.
- **A moving mesh moves by one matrix**. The original writes three floats on the mesh's node and the vertices go through it on the way to the card. The port had rewritten every moving corner into the set's buffer each frame. Its collision layer, likewise, tests a moving mesh whole by its sphere first.
- **A set streams in slices**. The original queues one read of a new set and serves it a slice a frame while it draws on. The port read and built the whole set in one frame. It now prepares the set on a thread while the Session counts the original's frames.
- **A line's voice is decoded while it plays**, on the original's timer callback, never all at once when the line starts. The port now decodes the next lines ahead, on a thread.
- **The world's audio runs at 22 050 Hz**. The port's device was running at the films' 44 100, so every world sound was being resampled.
- **The tie is decided once** (chapter 14).

The console's log of most of that round: the city at **40 to 50 ms a frame**, the player and the sky moved by the renderer, almost nothing re-uploaded. And one new lesson from the arrival in Anekbah: the set took 1.3 s on its thread against the half second of slices the original would allow, so the frame waited. The original simply waits on its reader, however long the disc takes, and so does the port now.

## Compared with the original

Put side by side with the 1999 engine, the pattern is clear.

|                      | the original                                                                                        | the port                                                                     |
|----------------------|-----------------------------------------------------------------------------------------------------|------------------------------------------------------------------------------|
| draw state           | the bucket order groups draws by blend and texture                                                  | a state cache at the API gives the same effect                               |
| per-frame memory     | fixed pools: the display list's node cap, shadows in the frame's own pools, a 160-buffer sound bank | down from ~720 to ~160 heap allocations a frame, heading toward pools        |
| scene programs       | pointers followed in place                                                                          | a small inline buffer                                                        |
| characters' geometry | posed and transformed on the CPU                                                                    | posed on the GPU, the player included, beyond the original                   |
| moving meshes        | one node matrix each                                                                                | one matrix each, the same                                                    |
| loading a set        | one read served a slice a frame                                                                     | a thread, released on the original's frame count                             |
| music                | decoded by branches                                                                                 | a table, cheaper than the original                                           |
| coincident faces     | free: quantised depth, strict test                                                                  | losers decided once per set and drawn a step back; per frame only for bodies |

The original's speed came from **structure**: an integer draw order, fixed pools, a quantised depth buffer, pointers walked in place. Most of the port's optimisation removed costs the port had *added* by using general-purpose containers and a GPU's float depth compare. Where the port does more than the original, posing on the GPU, it is because a Vita's CPU is spent elsewhere. It does not draw more characters. The crowd is the original's crowd, by the original's rule.

## 16. Where to go from here

---

You now have the whole machine in outline: a small executable running a large body of data, one loop, scripts that park instead of blocking, places that stay resident and solid, bodies driven by state graphs, a draw order that is a number, sound that is decided rather than mixed. And the replica: one engine with its decisions behind a boundary, reference and live backends, and a standard of evidence that asks every check to be able to fail.

For the next step, go by question:

- **"How exactly does X work?"** The manual, `manual/`, chapter by chapter, with the addresses and the checks.
- **"What is the evidence for that number?"** `docs/`: `FILE_FORMATS.md`, `ASSETS.md`, `SCRIPT_VM.md`, `UI.md`, `CUTSCENES.md`, `GAME_STATE.md`, `STREET_LIFE.md`. And `python3 tools/verify.py --list` names the check behind each figure.
- **"What is the standard for the port?"** `docs/PORTING.md`, the tiers and the boundary.
- **"What is being worked on?"** `todo/`: the optimisation record, the Vita handoff, the classic-Mac handoff, the task files.
- **"Why is it done this way, and what went wrong on the way?"** `CLAUDE.md` §1, the ground rules and the traps, each with the mistake that produced it.

### Glossary: Omikron ↔ Unity

| Omikron / OMK                 | the nearest Unity or OpenGL idea                | where it differs                                                      |
|-------------------------------|-------------------------------------------------|-----------------------------------------------------------------------|
| script context                | a coroutine                                     | parks by writing its own status word; resumed by events, never polled |
| trigger zone                  | a trigger collider with enter / exit / interact | its handlers are bytecode, its "fired" flag is in the save            |
| area / scene                  | a scene / an additive scene                     | two places resident at once, the hidden one still solid               |
| <code>.CTL</code> state graph | an Animator Controller                          | transitions are input bit masks; states carry gameplay data           |
| <code>.3D0</code> character   | a rigidly skinned hierarchy                     | one bone per vertex, no weights                                       |
| bucket key                    | render queue + sort key                         | a fixed integer order, no distance sort                               |
| camera editing                | a Timeline camera track                         | holds its last frame when it ends                                     |
| texture slot cache            | a texture atlas / cache                         | 58 slots, matched by file name alone                                  |
| renderer boundary             | a render pipeline                               | the engine submits decisions, not API calls                           |
| <code>dt = 30 / fps</code>    | <code>Time.deltaTime</code> in 1/30 s           | capped at 3.0: below 10 fps the game slows down                       |